



NOTES:

1. ALL EROSION CONTROL MEASURES ARE TO BE MAINTAINED DURING THE GRADING/BUILDING PHASE.
2. SILT FENCE SHALL BE PROVIDED WITH WIRE BACKING AND PLACED ON STEEL POST (1.33 LB/LF) SET ON A MAXIMUM OF 8' CENTERS. SEE CHP STD 600.00.
3. SILT FENCE SHALL BE TIED INTO A 6" X 6" TRENCH AND COVERED WITH A SUITABLE MATERIAL. SEE CHP STD 600.00.
4. EROSION CONTROL MEASURES SHOWN ARE APPROXIMATE. FIELD ADJUSTMENTS MAY BE NEEDED TO ENSURE THAT MEASURES ARE WORKING PROPERLY.
5. ANY SEDIMENT FROM THE SITE THAT IS CARRIED INTO THE STREET BY CONSTRUCTION TRAFFIC MUST BE REMOVED BY THE END OF THE WORK DAY.

**CITY OF HIGH POINT
NORTH CAROLINA
ENGINEERING SERVICES DEPARTMENT**

APPROVED ~~SEPTEMBER 12, 2016~~

BXP
.....
DIRECTOR

ISSUED 9-12-16

REVISIONS

9-12-16

STANDARD DRAWING FOR
TYPICAL LOT
FOR EROSION CONTROL

LOT EROSION.DWG

620.00

SHEET 1 OF 1